



# California Regional Water Quality Control Board

## Los Angeles Region



Linda S. Adams  
Agency Secretary

Recipient of the 2001 *Environmental Leadership Award* from Keep California Beautiful

Arnold Schwarzenegger  
Governor

320 W. 4th Street, Suite 200, Los Angeles, California 90013  
Phone (213) 576-6600 FAX (213) 576-6640 - Internet Address: <http://www.waterboards.ca.gov/losangeles>

Mr. Aziz Elatter  
Caltrans, District 7  
100 South Main Street  
Los Angeles, CA, 90012

### **WATER QUALITY CERTIFICATION FOR PROPOSED CLEANING OF AN EARTH DRAINAGE CHANNEL PM 33.4 LA-14 CITY OF SANTA CLARITA PROJECT (Corps' Project No. 2006-00965-MDC), UNNAMED TRIBUTARY TO SANTA CLARA RIVER, CITY OF SANTA CLARITA, LOS ANGELES COUNTY (File No. 06-044)**

Dear Mr. Elatter:

Regional Board staff has reviewed your request on behalf of Caltrans, District 7 (Applicant) for a Clean Water Act Section 401 Water Quality Certification for the above-referenced project. Your application was deemed complete on August 24, 2006.

I hereby issue an order certifying that any discharge from the referenced project will comply with the applicable provisions of sections 301 (Effluent Limitations), 302 (Water Quality Related Effluent Limitations), 303 (Water Quality Standards and Implementation Plans), 306 (National Standards of Performance), and 307 (Toxic and Pretreatment Effluent Standards) of the Clean Water Act, and with other applicable requirements of State law. This discharge is also regulated under State Water Resources Control Board Order No. 2003 - 0017 - DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges that have received State Water Quality Certification" which requires compliance with all conditions of this Water Quality Certification.

The Applicant shall be liable civilly for any violations of this Certification in accordance with the California Water Code. This Certification does not eliminate the Applicant's responsibility to comply with any other applicable laws, requirements and/or permits.

Should you have questions concerning this Certification action, please contact Dana Cole, Section 401 Program, at (213) 576-5733.

[Original signed by]  
Jonathan S. Bishop  
Executive Officer

November 16, 2006  
Date

**California Environmental Protection Agency**



*Our mission is to preserve and enhance the quality of California's water resources for the benefit of present and future generations.*

## DISTRIBUTION LIST

Oscar Balaguer  
State Water Resources Control Board  
Division of Water Quality  
P.O. Box 944213  
Sacramento, CA 94244-2130

Betty Courtney  
California Department of Fish and Game  
Streambed Alteration Team  
4949 View Ridge Avenue  
San Diego, CA 92123

Mark Cohen  
U.S. Army Corps of Engineers  
Regulatory Branch, Los Angeles District  
P.O. Box 532711  
Los Angeles, CA 90053-2325

Steven John  
U.S. Environmental Protection Agency  
600 Wilshire Boulevard, Suite 1460  
Los Angeles, CA 90017

Tim Vendlinski  
Supervisor, Wetlands Regulatory Office (WTR-8)  
US EPA, Region 9  
75 Hawthorne  
San Francisco, CA 94105

Ken Berg  
U.S. Fish and Wildlife Service  
6010 Hidden Valley Road  
Carlsbad, CA 92009

## ATTACHMENT A

### Project Information File No. 06-044

1. Applicant: Caltrans, District 7  
100 South Main Street  
Los Angeles, CA 90012  
  
Phone: (213) 897-0665      Fax: (213) 897-0685
2. Applicant's Agent: None
3. Project Name: Cleaning of an earth drainage channel Post Marker (PM) 33.4 LA-14 City of Santa Clarita
4. Project Location: Santa Clarita, Los Angeles County  
Longitude: 118.4270; Latitude: 34.4232  
Longitude: 118.4269; Latitude: 34.4233  
Longitude: 118.4271; Latitude: 34.4233  
Longitude: 118.4274; Latitude: 34.4233  
Longitude: 118.4275; Latitude: 34.4231  
Longitude: 118.4272; Latitude: 34.4231  
Longitude: 118.4267; Latitude: 34.4233  
Longitude: 118.4268; Latitude: 34.4233
5. Type of Project: Soft bottom channel debris and vegetation removal
6. Project Purpose: The proposed project will restore the channel to its original flow capacity.
7. Project Description: Current conditions in the channel affect the stream flow. The work will consist of removing debris and vegetation in an area approximately 20 feet wide and 50 feet long.  
  
The project is located on the northbound side of State Route (Highway) 14 at the Sand Canyon Road off ramp in the city of Santa Clarita in Los Angeles County.

## ATTACHMENT A

### Project Information File No. 06-044

8. Federal Agency/Permit: U.S. Army Corps of Engineers  
NWP No. 3 (Permit No. 2006-00965-MDC)
9. Other Required Regulatory Approvals: California Department of Fish and Game  
Streambed Alteration Agreement  
1600-2006-0090-R5
10. California Environmental Quality Act Compliance: On February 24, 2006 Caltrans determined that the proposed project is Categorical Exempt from CEQA pursuant to the CEQA Guidelines, Section 15061(b)(3) "no possibility of impact" if best management practices (BMPs) as described are followed.
11. Receiving Water: Unnamed tributary to Santa Clara River (Hydrologic Unit No. 403.51)
12. Designated Beneficial Uses: MUN\*, IND, PROC, AGR, GWR, FRSH, REC-1, REC-2, WARM, WILD, RARE, WET  
  
\*Conditional beneficial use
13. Impacted Waters of the United States: Non-wetland waters (vegetated streambed): 0.022 temporary acres (50 linear feet).
14. Dredge Volume: None
15. Related Projects Implemented/to be Implemented by the Applicant: The Applicant has not identified any related projects carried out in the last 5 years or planned for implementation in the next 5 years.
16. Avoidance/Minimization Activities: The Applicant has proposed to implement the following BMPs, including, but not limited to, the following:
- No work within the drainage will be conducted when the channel

## ATTACHMENT A

### Project Information File No. 06-044

is flowing.

- Work will cease if measurable rain is forecast to occur onsite within 72 hours as determined by the National Oceanic and Atmospheric Administration (NOAA).
- If removal of vegetation is done during the nesting season (February 15th through September 1st), then surveys will be conducted by a District Biologist to confirm presence/absence of any active nest in and adjacent to the work area.
- Native vegetation removed from the project site be replaced.
- The Willow trees that will be removed will be replaced at 3:1 ratio.
- Sediment and debris will not be allowed to enter any water sources.
- Silt fences, fiber rolls, and straw bales shall be used stabilize and protect the soil erosion on slopes.
- Check dams and sandbag barriers will be incorporated.
- Storm drain inlet protection will be placed at drain inlets.
- A surface water diversion plan (SWPPP) will be developed and submitted prior to construction.
- All work and staging areas will be performed within the existing access road footprint.

17. Proposed  
Compensatory  
Mitigation:

In-lieu fee.

**ATTACHMENT A**

**Project Information**  
**File No. 06-044**

18. Required  
Compensatory  
Mitigation:

The proposed compensatory mitigation in Item No. 17 above shall be required, and additionally as specified in Item Numbers 21 through 23 of Attachment B.

*See Attachment B Conditions of Certifications, Additional Conditions for modifications and additions to the above proposed compensatory mitigation.*

## ATTACHMENT B

### Conditions of Certification File No. 06-044

#### STANDARD CONDITIONS

Pursuant to §3860 of Title 23 of the California Code of Regulations (23 CCR), the following three standard conditions shall apply to this project:

1. This Certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to §13330 of the California Water Code and Article 6 (commencing with 23 CCR §3867).
2. This Certification action is not intended and shall not be construed to apply to any activity involving a hydroelectric facility and requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Certification application was filed pursuant to 23 CCR Subsection 3855(b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. Certification is conditioned upon total payment of any fee required pursuant to 23 CCR Chapter 28 and owed by the Applicant.

#### ADDITIONAL CONDITIONS

Pursuant to 23 CCR §3859(a), the Applicant shall comply with the following additional conditions:

1. The Applicant shall submit to this Regional Board copies of any other final permits and agreements required for this project, including, but not limited to, the U.S. Army Corps of Engineers' (ACOE) Section 404 Permit and the California Department of Fish and Game's (CDFG) Streambed Alteration Agreement. **These documents shall be submitted prior to any discharge to waters of the State.**
2. The Applicant shall adhere to the most stringent conditions indicated with either this certification, the CDFG's Streambed Alteration Agreement, or the ACOE Section 404 Permit.
3. The Applicant shall comply with all water quality objectives, prohibitions, and polices set forth in the *Water Quality Control Plan, Los Angeles Region (1994)*.
4. The Avoidance/Minimization activities proposed by the Applicant as described in Attachment A, No. 15, are incorporated as additional conditions herein.

## **ATTACHMENT B**

### **Conditions of Certification File No. 06-044**

5. The Applicant and all contractors employed by the Applicant shall have copies of this Certification, the approved maintenance plan, and all other regulatory approvals for this project on site at all times so they are familiar with all conditions set forth.
6. Fueling, lubrication, maintenance, operation, and storage of vehicles and equipment shall not result in a discharge or a threatened discharge to waters of the State. At no time shall the Applicant use any vehicle or equipment which leaks any substance that may impact water quality. Staging and storage areas for vehicles and equipment shall be located outside of waters of the State.
7. All excavation, construction, or maintenance activities shall follow best management practices to minimize impacts to water quality and beneficial uses. Dust control activities shall be conducted in such a manner that will not produce downstream runoff.
8. No construction material, spoils, debris, or any other substances associated with this project that may adversely impact water quality standards, shall be located in a manner which may result in a discharge or a threatened discharge to waters of the State. Designated spoil and waste areas shall be visually marked prior to any excavation and/or construction activity, and storage of the materials shall be confined to these areas.
9. All waste and/or dredged material removed shall be relocated to a legal point of disposal if applicable. A legal point of disposal is defined as one for which Waste Discharge Requirements have been established by a California Regional Water Quality Control Board, and is in full compliance therewith. Please contact Rodney Nelson, Land Disposal Unit, at (213) 620-6119 for further information.
10. The Applicant shall implement all necessary control measures to prevent the degradation of water quality from the proposed project in order to maintain compliance with the Basin Plan. The discharge shall meet all effluent limitations and toxic and effluent standards established to comply with the applicable water quality standards and other appropriate requirements, including the provisions of Sections 301, 302, 303, 306, and 307 of the Clean Water Act. This Certification does not authorize the discharge by the applicant for any other activity than specifically described in the 404 Permit.
11. The discharge shall not: a) degrade surface water communities and populations including vertebrate, invertebrate, and plant species; b) promote the breeding of mosquitoes, gnats, black flies, midges, or other pests; c) alter the color, create visual contrast with the natural appearance, nor cause aesthetically undesirable discoloration of the receiving waters; d) cause formation of sludge deposits; or e) adversely affect any designated beneficial uses.



## ATTACHMENT B

### Conditions of Certification File No. 06-044

12. The Applicant shall allow the Regional Board and its authorized representative entry to the premises, including all mitigation sites, to inspect and undertake any activity to determine compliance with this Certification, or as otherwise authorized by the California Water Code.
13. The Applicant shall not conduct any maintenance activities within waters of the State during a rainfall event, or at any period when site conditions would lead to excessive erosion. If any maintenance activities are to be held within five (5) days of a predicted rainfall event, the Applicant shall stage materials necessary to prevent water degradation on site, and shall ensure that all stabilization procedures are completed prior to the rainfall event.
14. Sediment removal at each phase shall not go beyond the extent as defined in the application packet.
15. The grading, stabilization and re-vegetation will be phased to limit the exposed or working face such that the graded area can be stabilized within 24 hours after the first prediction of rain during the 5-day forecast or within 24 hours after final grading of the phased area.
16. The Applicant shall utilize the services of a qualified biologist with expertise in riparian assessments during all construction activities where clearing involves areas to be partially cleared (i.e. some vegetation is to remain in the same reach or in an adjacent reach). The biologist shall be available on site during construction activities to ensure that all protected areas are marked properly and ensure that no vegetation outside the specified areas is removed. The biologist shall have the authority to stop the work, as necessary, if instructions are not followed. The biologist shall be available upon request from this Regional Board for consultation within 24 hours of request of consultation.
17. No activities shall involve wet excavations (i.e., no excavations shall occur below the seasonal high water table). A minimum **5-foot** buffer zone shall be maintained above the existing groundwater level. If construction or groundwater dewatering is proposed or anticipated, the Applicant shall file a **Report of Waste Discharge** to this Regional Board and obtain any necessary NPDES permits/Waste Discharge Requirements prior to discharging waste. Sufficient time should be allowed to obtain any such permits (generally 180 days). If groundwater is encountered without the benefit of appropriate permits, the Applicant shall cease all activities in the areas where groundwater is present, file a Report of Waste Discharge to this Regional Board, and obtain any necessary permits prior to discharging waste.
18. All project construction and/or maintenance activities not included in this Certification, and which may require a permit, must be reported to the Regional Board for appropriate permitting. Bank stabilization and grading, as well as any other ground disturbances, are subject to restoration and revegetation requirements, and may require additional Certification action.

## ATTACHMENT B

### Conditions of Certification File No. 06-044

19. All surface waters, including ponded waters, shall be diverted away from areas undergoing grading, construction, excavation, vegetation removal, and/or any other activity which may result in a discharge to the receiving water. If surface water diversions are anticipated, the Applicant shall develop and submit a **Surface Water Diversion Plan** (plan) to this Regional Board. The plan shall include the proposed method and duration of diversion activities, structure configuration, construction materials, equipment, erosion and sediment controls, and a map or drawing indicating the locations of diversion and discharge points. Contingency measures shall be a part of this plan to address various flow discharge rates. The plan shall be submitted prior to any surface water diversions. If surface flows are present, then upstream and downstream monitoring for the following shall be implemented:
- pH
  - temperature
  - dissolved oxygen
  - turbidity
  - total suspended solids(TSS)
  - Downstream TSS shall be maintained at ambient levels
  - Where natural turbidity is between 0 and 50 Nephelometric Turbidity Units (NTU), increases shall not exceed 20%. Where natural turbidity is greater than 50 NTU, increases shall not exceed 10%.

Analyses must be performed using approved US Environmental Protection Agency methods, where applicable. These constituents shall be monitored for on a daily basis during the first week of diversion and/or dewatering activities, and then on a weekly basis, thereafter, until the in-stream work is complete.

Results of the analyses shall be submitted to this Regional Board by the 15th day of each subsequent sampling month. A map or drawing indicating the locations of sampling points shall be included with each submittal. Diversion activities shall not result in the degradation of beneficial uses or exceedance of water quality objectives of the receiving waters. Any such violations may result in corrective and/or enforcement actions, including increased monitoring and sample collection.

20. The Applicant shall restore all areas of TEMPORARY IMPACTS to waters of the United States and all other areas of temporary disturbance which could result in a discharge or a threatened discharge to waters of the State. Restoration shall include grading of disturbed areas to pre-project contours and revegetation with native species. The Applicant shall implement all necessary Best Management Practices to control erosion and runoff from areas associated with this project.
21. The Applicant shall provide compensatory mitigation for the proposed permanent impacts to **0.022 acres** of vegetation within waters of the United States/Federal jurisdictional wetlands

## ATTACHMENT B

### Conditions of Certification File No. 06-044

by creating or restoring riparian habitat/Federal jurisdictional wetland habitat at a minimum **3:1** area replacement ratio (**0.66 acres**). As an alternative, the Applicant may provide adequate funding to a third party organization for the creation or restoration of a total of 0.66 acres of riparian habitat within waters of the United States/Federal jurisdictional wetlands. The mitigation site shall be located within the Santa Clara Watershed unless otherwise approved by this Regional Board.

22. The Applicant proposes funding to a third-party organization for the creation or restoration of a total of **0.66 acres** of vegetated streambed riparian habitat within waters of the United States/Federal jurisdictional wetlands. Funding shall apply to mitigation acreage only, exclusive of administrative costs. The mitigation site shall be located within the (Name of) Watershed unless otherwise approved by this Regional Board. The Applicant shall submit a **Proposed Mitigation Report** which shall include:
- (a) Documentation from the third party indicating that funds have been used for mitigation acreage only, which do not include administrative costs.
  - (b) The boundary of the mitigation site shall be clearly identified on a map of suitable resolution and quality and shall also be defined by latitude and longitude.
  - (c) The type(s) of mitigation shall be described (e.g., removal of exotics and/or replanting with native species, etc.)
  - (d) Success criteria shall be established.

**This information shall be submitted to this Regional Board for approval prior to any disturbance within waters of the United States** and shall include copies of all agreements made between the Applicant and a third party organization regarding compensatory mitigation efforts.

23. All open space and mitigation areas shall be placed within a conservation easement to ensure preservation in perpetuity. Documentation of proper easement placement shall be submitted to the Regional Board within one year.
24. The Applicant shall submit to this Regional Board **Annual Mitigation Monitoring Reports** by **January 1<sup>st</sup>** of each year for a minimum period of **five (5) years** after planting or until mitigation success has been achieved. The report shall describe in detail all of the project/construction activities performed during the previous year and all restoration and mitigation efforts; including percent survival by plant species and percent cover. This report shall include as a minimum, the following documentation:
- (e) Color photo documentation of the pre- and post-project and mitigation site conditions;
  - (f) Geographical Positioning System (GPS) coordinates in decimal-degrees format outlining the boundary of the project and mitigation areas;

## ATTACHMENT B

### Conditions of Certification File No. 06-044

- (g) The overall status of project including a detailed schedule of work;
  - (h) Copies of all permits revised as required in Additional Condition 1;
  - (i) Water quality monitoring results for each reach (as required) compiled in an easy to interpret format;
  - (j) A certified Statement of “no net loss” of wetlands associated with this project;
  - (k) Discussion of any monitoring activities and exotic plant control efforts; and
  - (l) A certified Statement from the permittee or his/her representative that all conditions of this Certification have been met.
25. Prior to any subsequent maintenance activities within the subject drainages, including clearing, maintenance by-hand, and/or the application of pesticides, the Applicant shall submit to this Regional Board a NOTIFICATION of any such activity. Notification shall include: (a) the proposed schedule; (b) a description of the drainage’s existing condition and/or capacity; (c) the area of proposed temporary impact within waters of the State; (c) a description of any existing aquatic resources (e.g., wetland/riparian vegetation); and (d) any proposed compensatory mitigation. Notifications must be submitted a minimum of **three (3) weeks** prior to commencing work activities.
26. All applications, reports, or information submitted to the Regional Board shall be signed:
- (a) For corporations, by a principal executive officer at least of the level of vice president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which discharge originates.
  - (b) For a partnership, by a general partner.
  - (c) For a sole proprietorship, by the proprietor.
  - (d) For a municipal, State, or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
27. Each and any report submitted in accordance with this Certification shall contain the following completed declaration:
- “I declare under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified

**ATTACHMENT B**

**Conditions of Certification  
File No. 06-044**

personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who managed the system or those directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Executed on the \_\_\_\_\_ day of \_\_\_\_\_ at \_\_\_\_\_.

\_\_\_\_\_  
\_\_\_\_\_  
(Signature)  
(Title)"

28. All communications regarding this project and submitted to this Regional Board shall identify the Project File Number **06-044**. Submittals shall be sent to the attention of the 401 Certification Unit.
29. Any modifications of the proposed project may require submittal of a new Clean Water Act Section 401 Water Quality Certification application and appropriate filing fee.
30. The project shall comply with the local regulations associated with the Regional Board's **Municipal Stormwater Permit** issued to Los Angeles County and co-permittees under NPDES No. CAS004001 and Waste Discharge Requirements Order No. 01-182. This includes the Standard Urban Storm Water Mitigation Plan (SUSMP) and all related implementing local ordinances and regulations for the control of stormwater pollution from new development and redevelopment. Requirements Order No. 00-108. This includes the Stormwater Quality Urban Impact Mitigation Plan (SQUIMP) and all related implementing local ordinances and regulations for the control of stormwater pollution from new development and redevelopment. The project shall also comply with all requirements of the National Pollutant Discharge Elimination System (NPDES) **General Permit** for Storm Water Discharges Associated with Construction Activity, Order No. 99-08-DWQ. All stormwater treatment systems shall be located outside of any water of the State and shall not be used as a wetland or riparian mitigation credit.
31. Coverage under this Certification may be transferred to the extent the underlying federal permit may legally be transferred and further provided that the Applicant notifies the Executive Officer at least 30 days before the proposed transfer date, and the notice includes a written agreement between the existing and new Applicants containing a specific date of coverage, responsibility for compliance with this Certification, and liability between them.
32. A copy of this Certification shall be kept at the project site during any period while project activities are being conducted, and shall be available upon request to any staff from this Regional Board.

## ATTACHMENT B

### Conditions of Certification File No. 06-044

33. The Applicant or their agents shall report any noncompliance. Any such information shall be provided verbally to the Executive Officer within 24 hours from the time the Applicant becomes aware of the circumstances. A written submission shall also be provided within five days of the time the Applicant becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected; the anticipated time it is expected to continue and steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance. The Executive Officer, or an authorized representative, may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.
34. *Enforcement:*
- (a) In the event of any violation or threatened violation of the conditions of this Certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under State law. For purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Certification.
  - (b) In response to a suspected violation of any condition of this Certification, the State Water Resources Control Board (SWRCB) or Regional Water Quality Control Board (RWQCB) may require the holder of any permit or license subject to this Certification to furnish, under penalty of perjury, any technical or monitoring reports the SWRCB deems appropriate, provided that the burden, including costs, of the reports shall be a reasonable relationship to the need for the reports and the benefits to be obtained from the reports.
  - (c) In response to any violation of the conditions of this Certification, the SWRCB or RWQCB may add to or modify the conditions of this Certification as appropriate to ensure compliance.
35. This Certification shall expire **five (5) years** from date of this Certification. The Applicant shall submit a complete application prior to termination of this Certification if renewal is requested.