

Notice of Section 401 Application Reception

File Number: 302024-13

Project Name: Veeder Dock Improvement

Received: 7/24/2024

Date Posted: 7/25/2024

End of 21 Day Public Comment Period: 8/15/2024

Project City: Huntington Beach

Project County: Orange

Applicant Organization: Veeder, Kurt

Applicant Name: Kurt Veeder

Waterboard Staff: TBA

Brief Description of Project:

Project Description: We are proposing to remove the existing 1,057.88 square foot L-shaped floating dock system - dock, (2) gangways. Replace with new 1,287.54 square foot L-shaped floating dock system 0- dock, (2) gangways. Reuse (3) existing 15" round concrete marina guide piling in their same location. No piling work is being proposed. The existing dock has deteriorated and must be replaced. In addition, the vessels intended to be berthed at this location are heavier and larger and therefore place a larger load on this floating dock. Increasing the dock and encompassing the (3) existing piling will alleviate the need to disturb the bay floor and add additional marina guide piling. This new design will allow the larger vessels to safely be berthed at this location.

Project Activities: The parts of the new floating dock system will be manufactured at the Huntington Beach Harbour Constructors Company facility. The parts will be placed on a trailer and towed to a public launch ramp where they will be floated to the project site by a small motorized barge vessel. The sections will be connected using pre-determined connection points. At each connection a catch bucket will be used as a precaution. Float the individual pieces to a public launch ramp using a small motorized barge vessel. The removed parts will be returned to the Harbour Constructors Company facility and dismantled. Those parts which can be recycled will be. All other parts will be properly disposed of at an upland disposal site.